

CITY OF GLENWOOD, ARKANSAS
LAKESHORE ST. – DENNIS ST. WATER MAIN REPLACEMENT

GW-03-20

BID PROPOSAL

<u>ITEM</u>	<u>QTY/UNIT</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
1.	1150 L.F.	Furnish and Install 3" SDR-21 PVC Water Main and Fittings including Trench Excavation, Laying, Bedding, Blocking and Backfilling per plans and specifications for the unit price of _____ Dollars and _____ Cents/L.F.	\$ _____	\$ _____
2.	350 L.F.	Directional Bore 3" Water Main per plans and specifications for the unit price of (Directional Bore includes the pipe) _____ Dollars and _____ Cents/L.F.	\$ _____	\$ _____

BID PROPOSAL
(Cont'd)

<u>ITEM</u>	<u>QTY/UNIT</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
3.	2 EA.	Furnish and Install 3" Gate Valve including valve box, valve marker and blocking per plans and specifications for the unit price of _____ Dollars and _____ Cents/EA.	\$ _____	\$ _____
4.	1 EA.	Furnish and Install 2" Blow-Off Valves with valve marker per plans and specifications for the unit price of _____ Dollars and _____ Cents/EA.	\$ _____	\$ _____
5.	12 EA.	Relocate existing water meters to proposed locations, Including 3/4" service tap, new meter box, setter, all necessary service line, and appurtenances per plans and specifications for the unit price of _____ Dollars and _____ Cents/EA.	\$ _____	\$ _____

BID PROPOSAL
(Cont'd)

<u>ITEM</u>	<u>QTY/UNIT</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
6.	2 EA.	Furnish and install 6"x3" tapping sleeve and valve assembly per plans and specifications for the unit price of (Includes 3" G.V.)		
		_____ Dollars and		
		_____ Cents/EA.	\$ _____	\$ _____
7.	50 L.F.	Open Cut and Repair Asphalt Surface per plans and specifications for the unit price of		
		_____ Dollars and		
		_____ Cents/LF.	\$ _____	\$ _____
8.	1 L.S.	Furnish all labor and install all equipment for testing and sterilization of treated mains and appurtenances per plans and specifications for the lump sum price of		
		_____ Dollars and		
		_____ Cents/L.S.	\$ _____	\$ _____

BID PROPOSAL
(Cont'd)

<u>ITEM</u>	<u>QTY/UNIT</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
9.	1 L.S.	Trench Safety per plans and specifications for the lump sum price of		
		_____ Dollars and		
		_____ Cents/L.S.	\$ _____	\$ _____
10.	1 L.S.	Furnish all labor and transportation to Mobilize all Equipment and material to complete the job for the Lump sum price of		
		_____ Dollars and		
		_____ Cents/L.S.	\$ _____	\$ _____
TOTAL BASE BID			\$ _____	

- NOTES:** 1) Miscellaneous items, directed work, connections, etc., not specifically listed but required to complete the proposed improvements to a complete and operational system shall be included in the Bid under the most appropriate Bid Item.
- 2) Time required to complete base bid work shall be 60 calendar days.
- 3) Contractor is solely responsible for the complete abandonment of all existing mains unless otherwise noted.